

BILANS ROBÓT ZIEMNYCH – Oś drogi gminnej							
Pikieta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Całk. obj. wykopu	Całk. obj. nasypu	Obj. netto
0+000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
0+015.3	0.1	0.9	1.0	6.93	1.04	6.93	-5.89
0+036.7	2.0	0.0	22.6	9.53	23.67	16.47	7.20
0+051.7	2.4	0.0	33.1	0.02	56.74	16.49	40.25
0+065.9	2.5	0.0	34.8	0.02	91.51	16.50	75.01
0+086.2	2.8	0.0	53.7	0.00	145.17	16.50	128.67
0+107.3	1.7	0.0	47.8	0.36	192.97	16.86	176.11
0+130.0	1.4	0.2	35.9	2.89	228.90	19.75	209.15
0+143.2	1.6	0.9	19.9	7.60	248.76	27.35	221.41
0+174.3	2.6	0.0	64.9	14.47	313.65	41.82	271.84
0+203.1	1.9	0.0	64.8	0.11	378.47	41.93	336.54
0+229.2	2.1	0.0	52.5	0.10	431.00	42.03	388.97
0+278.9	2.4	0.0	113.1	0.00	544.11	42.03	502.08
0+304.0	2.2	0.0	58.2	0.00	602.32	42.03	560.29
0+348.1	1.3	0.2	76.9	3.98	679.22	46.01	633.22
0+370.3	0.8	0.2	22.9	4.49	702.16	50.50	651.66
0+395.3	0.4	0.5	15.2	8.50	717.35	58.99	658.36
0+421.9	0.3	0.4	9.1	11.78	726.48	70.77	655.71
0+436.1	0.7	0.2	7.1	4.68	733.62	75.46	658.16
0+460.4	0.2	0.5	11.4	8.30	745.01	83.76	661.25
0+479.6	0.5	0.2	7.1	6.60	752.06	90.36	661.70
0+510.1	1.7	0.0	34.5	3.48	786.56	93.83	692.73
0+524.6	1.2	0.0	21.2	0.00	807.79	93.83	713.95
0+550.0	2.0	0.0	40.4	0.00	848.14	93.83	754.31
0+560.8	2.4	0.0	24.4	0.00	872.58	93.83	778.75
0+594.7	2.6	0.0	85.2	0.00	957.82	93.83	863.98
0+624.7	1.1	0.2	55.4	2.71	1013.20	96.54	916.66
0+649.4	1.0	0.3	24.9	5.95	1038.13	102.49	935.64
0+681.1	0.7	0.9	26.0	19.46	1064.15	121.95	942.20
0+706.9	0.7	0.6	18.1	19.66	1082.29	141.61	940.68
0+736.3	1.0	0.4	24.8	14.36	1107.13	155.97	951.16
0+761.1	1.6	0.2	32.1	7.87	1139.21	163.84	975.37
0+775.0	0.0	0.0	11.1	1.71	1150.35	165.54	984.81

Tab. 1 - Tabela robót ziemnych